

SHEET INDEX

GENERAL

- G1 COVER, VICINITY MAP AND SHEET INDEX
- G2 GENERAL NOTES AND ABBREVIATIONS
- **G3 GENERAL NOTES**
- **G4 EROSION CONTROL DETAILS**
- **G5 EROSION CONTROL DETAILS**
- G6 EXISTING SITE, ACCESS AND STAGING, EROSION AND SURVEY CONTROL
- G7 PROPOSED CONDITIONS AND SHEET KEY

CIVIL

C1 RELOCATED MAINTENANCE WAY PLAN, PROFILE AND SECTION

ECOLOGICAL

- E1 RIVER ISLAND LEFT BANK AREA PLAN
- E2 RIVER ISLAND LEFT BANK AREA CROSS SECTIONS
- RIVER ISLAND BACKWATER ALCOVE PLAN, F3 PROFILE AND CROSS SECTION
- SHOE ISLAND PLAN, PROFILE AND CROSS SECTIONS

DETAILS

- D1 TYPICAL BURIED LOG JAM DETAILS
- D2 TYPICAL TYPE 1 LOG JAM DETAILS
- D3 TYPICAL TYPE 2 LOG JAM DETAILS
- D4 TYPICAL TYPE 3 LOG JAM DETAILS
- D5 TYPICAL SHOW ISLAND ALCOVE LOG JAM DETAILS
- D6 TYPICAL ALCOVE LARGE WOOD AND FLOODPLAIN WOOD DETAILS
- D7 TYPICAL TURTLE HABITAT ENHANCEMENT DETAILS
- **D8 TYPICAL DETAILS**





V2 REVEGETATION DETAILS

SHEET INDEX

REVEGETATION V1 REVEGETAION PLAN

THE CONTRACTOR SHALL ATTEND A MANDATORY PRE-BID SITE MEETING.

THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH OWNER AND OWNER'S REPRESENTATIVE PRIOR TO MOBILIZING TO SITE AND BEGINNING CONSTRUCTION.

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE OREGON STATE DEPARTMENT OF TRANSPORTATION (ODOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL.

ODFW IN-WATER WORK PERIODS

WORK SHALL OCCUR DURING THE ODFW PERMITTED IN-WATER WORK PERIOD: JULY 15-AUGUST 31

EXISTING DATA

TOPOGRAPHIC DATA WAS COLLECTED BY INTER-FLUVE USING RTK AND TOTAL STATION IN DECEMBER 2013 AND DECEMBER 2014. BATHYMETRIC DATA WAS COLLECTED BY INTER-FLUVE USING RTK AND SONAR IN JANUARY AND FEBRUARY OF 2014.

HORIZONTAL DATUM: STATE PLANE NAD83 OREGON NORTH VERTICAL DATUM: NAVD88

HYDRAULIC MODELING BY INTER-FLUVE USING USACE HEC-RAS (4.1.0). MODEL CALIBRATED USING SURVEYED WATER SURFACE ELEVATIONS AND EXISTING HIGH WATER MARKS.

GIS DATA INCLUDING: AERIAL PHOTOGRAPHY, LIDAR, FISH USE, SURFACE SOILS INFORMATION, LAND OWNERSHIP, AND TRANSPORTATION ROUTES PROVIDED BY METRO.

SOILS

SUBSURFACE SOILS ARE EXPECTED TO BE SAND, GRAVEL, COBBLES, AND BOULDERS. EXCAVATIONS BELOW THE SURFACE MAY ENCOUNTER SANDY RIVER MUDSTONE AT SHALLOW DEPTHS. MUDSTONE SHALL BE KEPT SEPARATE FROM RIVER GRAVELS AND NOT USED FOR BACKFILL OF LARGE WOOD JAMS. VOLUME OF NON-NATIVE MATERIALS (E.G. ASPHALT, RIPRAP) ARE BASED ON SURVEY AND VISUAL COST ESTIMATES. CONTRACTOR SHALL CONDUCT OWN INVESTIGATIONS IF ADDITIONAL DATA IS REQUIRED AT NO ADDITIONAL COST.

UTILITIES

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

THE CONTRACTOR SHALL CALL (800-322-2344) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION.

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.

THE CONTRACTOR SHALL PROVIDE EQUIPMENT AND LABOR TO AID THE EFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO ADDITIONAL COST.

CONSTRUCTION STAKING

OWNER'S REPRESENTATIVE WILL PROVIDE STAKING OF PROJECT LIMITS, GRADE STAKES, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.

CONTRACTOR SHALL MEET WITH THE OWNER AND OWNER'S REPRESENTATIVE TO DEFINE AND MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF EQUIPMENT OR MATERIALS ONTO THE SITE.

THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST TO THE OWNER.

CONSTRUCTION MATERIALS

CONTRACTOR SHALL ALLOW FOR EXPANSION OF EXCAVATED MATERIAL AND COMPACTION OF PLACED MATERIAL AT NO ADDITIONAL MEASURE OR COST. MEASUREMENT AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE WITHOUT PRIOR WRITTEN APPROVAL.

LOCATION, ALIGNMENT, AND ELEVATION OF LOGS AND LOGS WITH ROOTWADS ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS AND MATERIAL SIZE.

ANY APPROVED NATIVE EXCESS MATERIAL SHALL BE STOCKPILED NEATLY IN AN APPROVED LOCATION OF THE STOCKPILE AND STAGING AREA. AT COMPLETION OF WORK, THE NATIVE MATERIAL SHALL BE DISPOSED OF IN THE IDENTIFIED DISPOSAL LOCATION. THE CONTRACTOR WILL DECONSTRUCT/DEMOLISH AND LEGALLY DISPOSE OF THE LOWER BARN AND ALL CONCRETE AND BUILDING MATERIALS ASSOCIATED WITH THE BARN SITE. THE CONTRACTOR WILL DISPOSE OF NON-NATIVE MATERIAL FROM THE LEFT BANK CLEANUP AREA IN AN APPROVED, LEGAL OFFSITE DISPOSAL FACILITY.

CONSTRUCTION ACCESS/TRAFFIC CONTROL

CONTRACTOR SHALL SUBMIT AN ACCESS, STAGING, AND STOCKPILE PLAN TO METRO FOR APPROVAL PRIOR TO MOBILIZATION.

PUBLIC ACCESS TO/ALONG ROADWAYS SHALL BE MAINTAINED AT ALL TIMES.

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR OBTAINING ANY REOUIRED TRAFFIC CONTROL OR ACCESS PERMITS.

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR PROVIDING ANY REQUIRED TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO, SIGNAGE AND FLAGGERS.

THE CONTRACTOR SHALL PLACE SIGNAGE UPSTREAM OF WORK AREA IN A MANNER TO DISCOURAGE RIVER USERS FROM ENTERING THE WORK AREA.

ALL SAPLINGS AND TREES TO BE TRANSPLANTED OR REMOVED SHALL BE CLEARLY MARKED AND APPROVED BY METRO

ALL EQUIPMENT, MATERIALS, AND PERSONNEL SHALL REMAIN WITHIN THE LIMITS OF DISTURBANCE

THE CONTRACTOR SHALL KEEP THE WORK AREAS IN NEAT CONDITION, FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.

CONTRACTOR SHALL IMPLEMENT MEASURES TO CONTROL AND MINIMIZE WIND BLOWN DUST FROM THE SITE.

ALL DISTURBED AREAS INCLUDING ROADS, DRIVEWAYS AND ACCESS ROUTES SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AND RE-VEGETATED PER PLANS.

ALL DISTURBED AREAS OUTSIDE THE LIMITS OF DISTURBANCE SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AT NO ADDITIONAL COST TO THE OWNER.

EROSION CONTROL

CONTRACTOR SHALL BE SOLELY RESPONSIBLE AT OWN EXPENSE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION CONTROL REGULATIONS AND TO MAINTAIN CLEAN ACCESS ROUTES.

RIVER ISLAND SOUTH PRELIMINARY DESIGN	
METRO	
CLACKAMAS COUNTY, OREGON	





				ען מס		MD
				NP, LK	EA,IVID, IVIC	IVID
				DRAWN	DESIGNED	CHECKED
				MC	IAN 2015	130235
				IVIC	JAN 2015	130233
				APPROVED	DATE	PROJECT
NO.	BY	DATE	REVISION DESCRIPTION			

FISH RESCUE

ALL FISH TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA WILL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUME OF FRESH RIVER WATER.

EXPERIENCED PERSONNEL.

WETLANDS AND WATERS OF THE US

THE ORDINARY HIGH WATER (OHW) OR APPROXIMATE LOW WATER LINES DISPLAYED IN THIS DESIGN PACKAGE WERE DELINEATED BY INTER-FLUVE STAFF IN 2014 AND 2015, AND ARE BASED UPON ANALYSIS, MODELING, AND BEST PROFESSIONAL JUDGEMENT. A WETLAND DELINEATION HAS NOT BEEN PERFORMED.

THE OHW LINES DO NOT REPRESENT JURISDICTIONAL BOUNDARIES. WITHIN THE STATE OF OREGON. THE ARMY CORPS OF ENGINEERS AND THE DEPARTMENT OF STATE LANDS HAVE THE FINAL AUTHORITY IN DETERMINING WATERS AND WETLANDS BOUNDARIES AND REGULATIONS.

ABBREVIATIONS

SMPs	BEST MANAGE
CY	CUBIC YARDS
DBH	DIAMETER AT E
DIA	DIAMETER
	EAST
A	EACH
T	FOOT
TR	FULLY THREAD
IORIZ	HORIZONTAL
NTS	NOT TO SCALE
٧	NORTH
.B	POUND
W	LARGE WOOD
VAX	MAXIMUM
ИIN	MINIMUM
DDFW	OREGON DEPA
۲D	ROAD
RW	ROOTWAD
5	SOUTH
ГҮР	TYPICAL
/ERT	VERTICAL
N	WEST

ALL FISH RESCUE EFFORTS SHALL BE SUPERVISED BY THE OWNER'S REPRESENTATIVE AND SHALL BE PERFORMED BY PERSONNEL EXPERIENCED WITH THE COLLECTION AND HANDLING OF SALMONIDS FROM CONSTRUCTION SITES.

CAPTURED FISH SHALL BE IMMEDIATELY RELEASED INTO THE RIVER AT AREAS SELECTED BY

BEST MANAGEMENT PRACTICES

BREAST HEIGHT

ED ROD

ARTMENT OF FISH AND WILDLIFE



GENERAL NOTES AND ABBREVIATIONS

TURTLE BEST MANAGEMENT PRACTICES

- A. ALL WORK SHALL CONFORM TO THE BELOW LIST OF OREGON DEPARTMENT OF FISH AND WILDLIFE (ODFW) TURTLE BEST MANAGEMENT PRACTICES TO THE EXTENT PRACTICABLE. THE CONTRACTOR SHALL WORK WITH THE OWNER'S REPRESENTATIVE TO PROTECT TURTLE AND TURTLE HABITAT THROUGHOUT THE CONSTRUCTION PROJECT.
 - 1. CONTRACTOR SHALL MINIMIZE TEMPORARY CHANGES TO THE HYDROLOGY OR SEDIMENTATION RATES OF WATERBODIES SUPPORTING TURTLES FROM GROUND DISTURBANCES WITHIN 500 FT OF NATIVE TURTLE HABITAT OR WITHIN 150 FEET OF WATERWAYS THAT FLOW TO NATIVE TURTLE HABITAT.
 - 2. CONTRACTOR SHALL USE JUTE MATTING, WEED FREE NATIVE STRAW, MULCH BERMS OR OTHER NATURAL FIBER EROSION CONTROL PRODUCTS ON DISTURBED AREAS.
 - 3. CONTRACTOR SHALL NOT USE PRODUCTS WITH PLASTIC MESH THAT CAN ENTANGLE WILDLIFE.
 - 4. CONFIRMED TURTLE NESTS SHALL BE MARKED WITH TEMPORARY FLAGGING AND EXCLUDED FROM THE WORK ARE WITH SILT FENCE. FLAGGING AND FENCING SHALL BE REMOVED IMMEDIATELY UPON PROJECT COMPLETION.
 - 5. MINIMIZE THE FOOTPRINT OF GROUND DISTURBANCE DURING ACCESS TO THE EXTENT PRACTICABLE.
 - 6. LOCATE PROJECT STAGING AREA AND OTHER CONSTRUCTION RELATED SUPPORT FEATURES (E.G. EQUIPMENT FUELING STATIONS) AT LEAST 50 FEET FROM WATERBODIES AND IDENTIFIED TURTLE NESTING HABITAT.
 - 7. IF SMALL ENGINE EQUIPMENT SUCH AS PUMPS FOR TEMPORARY WATER MANAGEMENT MUST BE USED WITHIN 50 FEET OF A WATERBODY OF KNOWN OR SUSPECTED TURTLE NEST SITES, PLACE IN A LEAK PROOF CONTAINER TO CONTAIN SPILLS FROM BROKEN FUEL LINES OR ACCIDENTAL SPILLS.

B. INSPECTION

- 1. CONTRACTOR SHALL ANTICIPATE THAT ALL WORK AREAS WILL BE INSPECTED BY A QUALIFIED BIOLOGIST EXPERIENCED WITH TURTLES BEFORE CONSTRUCTION AND AT LEAST ONCE DURING CONSTRUCTION.
- 2. QUALIFIED BIOLOGIST SHALL PROVIDE OWNER AND OWNER'S REPRESENTATIVE WITH SUGGESTED VISUAL SURVEY AND TURTLE HABITAT EVALUATION PROTOCOL FOR ONGOING MONITORING DURING THE PROJECT

TREE SALVAGE

ALL TREES AND SLASH REMOVED FOR CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED WITHIN LIMITS OF DISTURBANCE. STOCKPILED TREE/SLASH SHALL BE REINCORPORATED INTO FINISHED PROJECT.

ALL TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOTWAD AND UTILIZED IN THE LOGJAMS AS DIRECTED BY OWNER'S REPRESENTATIVE.

LIVE TREES

ALL TREES NOT MARKED FOR REMOVAL SHALL BE LEFT STANDING UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT DEBARK OR DAMAGE LIVE TREES.

KEEP HEAVY EQUIPMENT OUT OF CANOPY DRIP LINE OF EXISTING TREES TO REMAIN.

PRELIMINARY QUANTITIES TABLES:

Fill Volumes							
			Fill Dim	Duration of			
Wetland/Waterbody Name	Length (ft)	Width (ft)	Depth (ft)	Area ² (sq. ft.)	Volume (c.y.)	impact (days)	Material
Clackamas River - Shoe Island Area	260	45	1.5 - 10.5	11700	1800 (1350 below OHW)	permanent	Native gravel and cobble and 146 logs
Clackamas River - Alcove Area	400	45	1.5 - 5	18000	1040 (650 below OHW)	permanent	Native gravel and cobble and 151 logs
Clackamas River - Left Bank Area	270	40	1.5 - 5	10800	2010 (1490 below OHW)	permanent	Native Material (gravel, cobble soil and mudstone) and 179 logs
Notes: 179 logs ¹ Fill dimensions represent the summation of discontinguous areas. ² Fill area includes spaces between placed logs(e.g. the entire footprint of the log iam).							

Removal Volumes							
			Removal [Duration of			
Wetland/Waterbody Name	Length (ft)	Width (ft)	Depth (ft)	Area (sq. ft.)	Volume (c.y.)	impact (days)	Material
Clackamas River - Shoe Island Area	470	50	10.5	23500	3840 (3190 below OHW)	7-10	Native gravel and cobble
Clackamas River - Alcove Area	240	40	3 - 6	9600	1720 (1070 below OHW)	10-15 ²	Road fill/native gravel and cobble
Clackamas River - Left Bank Area	700	40	2 - 5	28000	4940 (3700 below OHW)	10-15 ³	Road fill/concrete trash/native material(gravel,cobble soil and mudstone)

Notes:

¹Removal dimensions represent the summation of discontinguous areas.

²Removal of road fill in the alcove area will be permanent

³Removal of remnant quarry material will be permanent

ME					RP, LK	EA,MB, MC	MB	RIVER
2					DRAWN	DESIGNED	CHECKED	
έ					MC	JAN 2015	130235	
<u>.</u>					APPROVED	DATE	PROJECT	
اد	NO.	BY	DATE	REVISION DESCRIPTION				

ISLAND SOUTH PRELIMINARY DESIGN METRO CLACKAMAS COUNTY, OREGON







GENERAL NOTES

SHEET

G3 OF 22

EROSION/SEDIMENTATION CONTROL (ESC) PLAN

THE EROSION AND SEDIMENT CONTROL (ESC) PLAN PROVIDED IS FOR INFORMATIONAL PURPOSES ONLY, THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION CONTROL MEASURES TO COMPLY WITH APPLICABLE REGULATIONS.

THE RECOMMENDATIONS FOR AN ESC PLAN INCLUDED HEREIN WILL PROVIDE A GUIDELINE FOR THE CONTRACTOR TO DEVELOP AND IMPLEMENT AN ESC PLAN.

- THE IMPLEMENTATION OF AN ESC PLAN AND THE CONSTRUCTION MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED
- THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE Β. CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD. NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- C. ESC FACILITIES AS APPROXIMATELY SHOWN ON THIS PLAN ARE TO BE CONSTRUCTED PRIOR TO CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT ENTER SURFACE WATERS, THE DRAINAGE SYSTEM, OR VIOLATE APPLICABLE WATER STANDARDS
- D. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND F. MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- F. THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
- STABILIZED CONSTRUCTION ENTRANCES AND ADDITIONAL MEASURES MAY BE REQUIRED AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT TO ENSURE ALL ACCESS ROADS ARE KEPT CLEAN AT NO ADDITIONAL COST.

INSPECTION AND MAINTENANCE

ALL ESC FACILITIES SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL ESC FACILITIES SHALL BE INSPECTED DAILY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD AND AFTER EVENTS **EXCEEDING 2 HOURS DURATION.**

CONTRACTOR'S ESC RECORD

WEEKLY REPORTS SUMMARIZING THE SCOPE OF INSPECTIONS, THE PERSONNEL CONDUCTING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN, AND ACTIONS TAKEN AS A RESULT OF THESE INSPECTIONS SHALL BE PREPARED AND RETAINED ON SITE BY THE CONTRACTOR. IN ADDITION, A RECORD OF THE FOLLOWING DATES SHALL BE INCLUDED IN THE **REPORTS:**

- WHEN MAJOR GRADING ACTIVITIES OCCUR.
- DATES OF RAINFALL EVENTS EITHER EXCEEDING 2 HOURS DURATION OR MORE 2. THAN 0.5 INCHES/24 HOURS
- WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON 3. SITE, OR ON A PORTION OF THE SITE.
- WHEN STABILIZATION MEASURES ARE INITIATED FOR PORTIONS OF THE SITE.
- ESC RECORDS SHALL BE MADE AVAILABLE TO THE OWNER AND OWNER'S REPRESENTATIVE ON REQUEST AND SHALL BE PROVIDED FOR REVIEW AND APPROVAL PRIOR TO APPLICATION FOR PAYMENT.

STABILIZE SOILS AND PROTECT SLOPES

FROM MAY 1 THROUGH SEPTEMBER 30, ALL EXPOSED SOILS SHALL BE PROTECTED FROM EROSION BY MULCHING, HYDROSEED COVERING, OR OTHER APPROVED MEASURES WITHIN THREE DAYS OF GRADING. FROM OCTOBER 1 THROUGH APRIL 30, ALL EXPOSED SOILS MUST BE PROTECTED WITHIN 2 DAYS OF GRADING. SOILS SHALL BE STABILIZED BEFORE A WORK SHUTDOWN, HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST. SOIL STOCKPILINGS MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES. HYDROSEED ALL DISTURBED AREAS AS SOON AS PRACTICAL NOT INDICATED IN THE CONTRACT DOCUMENTS FOR OTHER PERMANENT STABILIZATION MEASURES.

DESIGN, CONSTRUCT, AND PHASE CUT AND FILL SLOPES IN A MANNER THAT WILL MINIMIZE EROSION. REDUCE SLOPE VELOCITIES ON DISTURBED SLOPES BY PROVIDING TEMPORARY BARRIERS. STORMWATER FROM OFF SITE SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON SITE.

AFTER FINAL SITE STABILIZATION

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BEST MANAGEMENT PRACTICES (BPMs) ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED FROM THE SITE OR INCORPORATED INTO FINISHED GRADING. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED.

RIVER DIVERSION

DIVERSION MAY BYPASS THE RIVER AROUND SMALLER WORK AREAS AT CONTRACTOR'S DISCRETION.

DEWATERING OF IN-CHANNEL WORK AREA(S) SHALL OCCUR CONCURRENT WITH FISH RESCUE. CONTRACTOR SHALL COORDINATE WITH METRO FOR FISH RESCUE. CONTRACTOR SHALL PROVIDE METRO AMPLE TIME TO SCHEDULE FISH RESCUE. IF DIVERSION FAILS DUE TO CONTRACTOR NEGLIGENCE, FISH RESCUE SHALL BE REPEATED BY METRO'S REPRESENTATIVE AT CONTRACTOR'S EXPENSE.

IF ADDITIONAL PUMPING IS REQUIRED TO DEWATER DURING CONSTRUCTION, PUMPED DISCHARGE SHALL RELEASE SEDIMENT-LADEN WATER AT AN UPLAND DISCHARGE LOCATION IN A MANNER THAT DOES NOT CAUSE EROSION, CONTAMINATION OR INCREASE TURBIDITY OF SURFACE WATERS. (SEE CONSTRUCTION DEWATERING).

OWNER'S REPRESENTATIVE SHALL APPROVE DEWATERING DISCHARGE LOCATION PRIOR TO IMPLEMENTATION.

CONSTRUCTION DEWATERING

CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO AVOID THE RELEASE OF SEDIMENT-LADEN WATER TO SURFACE WATERS. SEDIMENT LADEN WATER MAY BE PUMPED TO AN UPLAND DISCHARGE LOCATION AND ALLOWED TO SHEET FLOW THROUGH EXISTING VEGETATION BEFORE INFILTRATING INTO THE GROUND. IF THIS METHOD IS NOT SUFFICIENT TO PREVENT RETURN OF TURBID WATER TO THE RIVER, A 'DIRT-BAG' OR SEDIMENT RETENTION STRUCTURE MAY BE REQUIRED AS NECESSARY TO COMPLY WITH LAWS AND PERMIT REQUIREMENTS AT NO ADDITIONAL COST TO THE OWNER.

CONTRACTOR SHALL PROVIDE VISQUINE OR GEOTEXTILE LINER OR PLYWOOD OR METAL PLATING AS NECESSARY TO DISSIPATE PUMP DISCHARGE JET TO PREVENT EROSION.

EROSION CONTROL SEED MIX:

SEED MIX SPECIFICATION

Scientific name	Common name
Deshampsia elongata	Slender hairgrass
Agrostis exarata	Spike bentrgrass
Prunella vulgaris	Self-heal

SEED MIX APPLICATION

IN LIMITS OF DISTURBANCE ABOVE OHW.







MC JAN 2015 130235 METRO NO. BY DATE REVISION DESCRIPTION DATE PROJECT	RP, LK EA,MB, MC MB RIVER ISLAND SOUTH PRELIMINARY DESIGN Drawn Designed CHECKED MB NC IAN 2015 120235
--	--



SILT FENCES:

- 1. THE SILT FENCE SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, SILT FENCE SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND BOTH ENDS SECURELY FASTENED TO THE POST. ALTERNATIVELY, OVERLAP AND INTERLOCK TWO POSTS WITH ATTACHED FABRIC AS REQUIRED TO MEET APPLICABLE REGULATIONS.
- 2. THE SILT FENCE IS TO BE INSTALLED AT LOCATIONS SHOWN ON THE PLAN. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 18 INCHES.
- 3. THE SILT FENCE SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6 INCHES. ALL EXCAVATED MATERIAL FROM SILT FENCE INSTALLATION SHALL BE BACK-FILLED AND COMPACTED ALONG THE ENTIRE DISTURBED AREA.
- STANDARD OR HEAVY DUTY SILT FENCE SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2 INCHES X 2 4. INCHES POST INSTALLATION.
- 5. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED, OR AS DIRECTED BY OWNER'S REPRESENTATIVE.





BULK BAG NOTES:

- 1. BULK BAG COFFERDAM SHALL BE CONSTRUCTED OF SEVERAL UNITS OF BULK BAGS FILLED WITH WASHED GRAVEL, AND ABUTTED SIDE BY SIDE TO CREATE A ROW THAT ISOLATES THE CONSTRUCTION SITE FROM THE RIVER.
- 2. IF WATER DEPTH EXCEEDS 85% OF THE BULK BAG HEIGHT, AN ADDITIONAL TOP ROW OF BULK BAGS SHALL BE INSTALLED, SUPPORTED BY TWO BOTTOM ROWS OF BULK BAGS.
- 3. BULK BAG COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY STANDARD SANDBAGS PLACED IN ROWS ON TOP OF COFFERDAM. AND AT TOE OF COFFERDAM. THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM ON THE WORK AREA SIDE OF THE COFFERDAM WITH OUTWARD EDGE OF SHEETING MINIMUM 4-FEET FROM TOE OF COFFERDAM. THE DRAPED PORTION OF PLASTIC SHEETING SHALL BE PINNED TO THE CHANNEL BED BY MINIMUM TWO ROWS OF STANDARD SANDBAGS.
- 4. THE OUTWARD EDGE OF PLASTIC SHEETING ON WORK AREA SIDE SHALL BE TOED INTO THE CHANNEL BED MINIMUM 1-FT. TOEING IN THE OUTWARD EDGE OF PLASTIC SHEETING SHALL OCCUR AFTER THE COFFERDAM IS CLOSED TO PREVENT TURBIDITY RELEASE TO THE WATERWAY.
- 5. IF POSSIBLE, THE COFFERDAM SHALL BE EXTENDED ONTO A GRAVEL BAR AND OUT OF THE WATER. IF THE END MUST BE TERMINATED AT THE RIVERBANK, THE COFFERDAM SHALL BE TIGHTLY SEALED TO THE GROUND BY PLASTIC SHEETING AND STANDARD SANDBAGS. MULTIPLE LAYERS OF SANDBAGS MAY BE REQUIRED TO FORM A WATERTIGHT SEAL.
- 6. BULK BAGS SHALL BE WATERPROOF CUBE-SHAPED POLYPROPYLENE WOVEN FABRIC BAGS WITH FULLY OPEN TOP, FLAT BOTTOM, FOUR LOOPS, MINIMUM 2-TON WEIGHT CAPACITY, MINIMUM 5:1 SAFETY FACTOR.
- 7. PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. ROLL LENGTH SHALL BE LONG ENOUGH TO ENSURE THAT ENTIRE LENGTH OF COFFERDAM WILL BE COVERED WITHOUT A SEAM. MINIMUM 12-FT WIDE ROLL SHALL BE USED FOR SINGLE LAYER BULK BAG COFFERDAM. MINIMUM 16-FT WIDE ROLL SHALL BE USED FOR 2-LAYER STACKED BULK BAG COFFERDAM.
- 8. CONTRACTOR SHALL PROVIDE PUMPING SUFFICIENT FOR A NET INFLOW TO THE WORK AREA, AND DISCHARGE TURBID WATER TO UPLAND FLOODPLAIN.
- 9. BULK BAG COFFERDAM SHALL BE COMPLETELY REMOVED AFTER CONSTRUCTION IS COMPLETED AND TURBIDITY HAS BEEN REMOVED.
- 10. ALTERNATE COFFERDAM MATERIALS AND CONFIGURATIONS MAY BE ALLOWED BUT SHALL NOT BE IMPLEMENTED WITHOUT REVIEW AND APPROVAL BY THE OWNER OR OWNER'S REPRESENTATIVE. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS AND/OR VENDOR CUT SHEETS FOR SUBSTITUTIONS.
- 11. IF NECESSARY, GAPS BETWEEN BULK BAGS SHALL BE FILLED WITH WASHED STREAM GRAVEL TO IMPROVE COFFERDAM SEAL.



RIVER ISLAND SOUTH PRELIMINARY DESIGN MC JAN 2015 JAN 2015 130235 PROJECT CLACKAMAS COUNTY, OREGON	Metro
--	-------



EROSION CONTROL DETAILS

Preliminary Not for Construction

SHEET

G5 ^{OF} 22



C.							
	0	300	FFFT	600			
St		LEGE	ND				
All and			 MPORARY CON	ISTRUCTIO	N STAGING		
The second secon		TU SPI	RTLE CROSSING RING 2015)	G BMPs (TO	O BE INITIATED		
K		— — EXI (1	STING CONTO FT. INTERVALS)	JRS			
500		- <u> </u>	OPERTY LINES				
0	ОН	OR	DINARY HIGH	WATER			
11		EXI	STING ROAD				
Par las	_	TEI	MPORARY ACC	ESS			
3-6		EXI	STING ROAD T	O BE DECC	MMISSIONED		
510	→→ EXISTING CULVERT						
1	TEMPORARY COFFERDAM, SEE $\begin{pmatrix} 2\\ G5 \end{pmatrix}$						
* 3	-00	- TU	RBIDITY CURTA		$\frac{1}{64}$		
. (x	—×— SIL	T FENCE, SEE	(1) (G5)			
<u> 1</u>	900 — 🕰 SURVEY BENCHMARK						
Sing Early	1. NATUI FOR T JULY 6	RAL COLOR OR HE PORTLAND 5 THROUGH 14	THO-RECTIFIEI METROPOLITA , 2012.	d Aerial II An Area Co	MAGERY OLLECTED		
	2. EXISTING CONTOURS DERIVED FROM LIDAR DATA COLLECTED IN 2007.						
	3. PROPE	ERTY LINES ARI	E APPROXIMAT	E.			
	SELEC	TED SUR	VEY BEN	СНМА	RKS		
	Point #	Northing	Easting	Elevation	Description		
200	900	626562.6540	713311.7400	190.417	BM		
2	3435	625763.030	714122.357	193.381	твм		
13	30000028	628619.094	714299.481	195.435	REBAR		
155	30000051	628507.282	714333.521	192.740	REBAR		
A C		The second	FD	WARDS	Per		
TES OF	AMERICA		212	Non Com			
		2.20	N	(teas	Official Contraction		

EXISTING SITE ACCESS AND	
STAGING, EROSION AND	
SURVEY CONTROL	(

G6 OF 22



	<u>Zar</u>
0	300 600
SCA	LE IN FEET
IF	
<u>LL</u>	GEND
	TEMPORARY CONSTRUCTION STAGING
	NATIVE SOILS DISPOSAL AREA
	PROPOSED SELECTIVE GRADING AND ASPHALT REMOVAL AREA
	FILL REMOVAL AREA
	PROPOSED SHOE ISLAND ALCOVE
	PROPOSED ROAD PRISM REMOVAL
	PROPOSED TURTLE NESTING AREA
	EXISTING CONTOURS (1 FT. INTERVALS)
	PROPERTY LINES
	TEMPORARY COFFERDAM
-000	TURBIDITY CURTAIN
	APPROXIMATE LOW WATER
	LIMITS OF DISTURBANCE
	EXISTING ROAD TO BE DECOMMISSIONED
	EXISTING ACCESS ROAD
	TEMPORARY ACCESS ROAD
	RELOCATED MAINTENANCE WAY
-	BURIED LOG JAM, SEE SHEET D1
2	TYPE 1 LOG JAM, SEE SHEET D2
~	TYPE 2 LOG JAM, SEE SHEET D3
~	TYPE 3 LOG JAM, SEE SHEET D4
~	SHOE ISLAND ALCOVE LOG JAM, SEE SHEET D5
	SHOE ISLAND LARGE WOOD, SEE $\begin{pmatrix} 1 \\ D6 \end{pmatrix}$
	FOREST WOOD PLACEMENT
2	FLOODPLAIN LARGE WOOD, SEE $\left(\frac{2}{D6}\right)$
DTES:	
L. NATURAL COLO PORTLAND ME	OR ORTHO-RECTIFIED AERIAL IMAGERY FOR THE

- 2. EXISTING CONTOURS DERIVED FROM LIDAR DATA COLLECTED IN 2007.
- 3. PROPERTY LINES ARE APPROXIMATE.

2012.

PROPOSED CONDITIONS AND SHEET KEY



LE	GEND
	TEMPORARY CONSTRUCTION STAGING
	PROPOSED SELECTIVE GRADING AND ASPHALT REMOVAL AREA
	EXISTING CONTOURS (1 FT. INTERVALS)
>	ROLLING WATER BAR
≺	EXISTING CULVERT
	PROPOSED CULVERT
	PROPERTY LINES
00	TURBIDITY CURTAIN
_	RELOCATED MAINTENANCE WAY
	EXISTING ROAD TO BE DECOMMISSIONED
	EXISTING ACCESS ROAD

Juve	
a, Suite 101 97031 03 14900	

RELOCATED MAINTENANCE	SI	HEET
WAY PLAN PROFILE AND		
SECTION	C1	of 22







PHOTO - EXISTING LEFT BANK CONDITIONS



RP, LK	EA,MB, MC	MB	RI
DRAWN	DESIGNED	CHECKED	
MC	JAN 2015	130235	
APPROVED	DATE	PROJECT	

METRO

CLACKAMAS COUNTY, OREGON

DATE

REVISION DESCRIPTION



RIVER ISLAND LEFT BANK AREA CROSS SECTIONS

SHEET

E2 OF 22



'	RIVER ISLAND BACKWATER	SHEET
and the second se		
line.	ALCOVE PLAN, PROFILE AND	$E^{2} \cap E^{2}$
n, Suite 101 : 97031 03 Loom	CROSS SECTION	E3 ⁰¹ ZZ



PLAN - SHOE ISLAND 1"=100'



PROFILE - SHOE ISLAND ALCOVE





CLACKAMAS RIVER



Α E4











Cinter fluve 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.398.9003 swachtaritum.com



TYPICAL TYPE 1 LOG JAM DETAILS

SHEET D2 OF 22









LEGEND

*	LOG JAM WOOD LAYER 1
*	LOG JAM WOOD LAYER 2
*	LOG JAM WOOD LAYER 3
	EXISTING CONTOURS (1FT INTERVAL)
	APPROXIMATE LOW WATER





TYPICAL TYPE 3 LOG JAM DETAILS



D5 ^o^F 22





GRADATION TABLE

TURTLE NES
SOIL/SUBSTRA
FINE CLAY
LOAM
SAND
1/4" ROUNDED AGG

ING G	ROUND SUBSTRATE
E	% OF TOTAL MIX
	25 OR LESS
	25
	25-50
EGATE*	25 OR LESS

* ROUNDED AGGREGATE SHALL NOT INCLUDE FINES



TYPICAL TURTLE HABITAT ENHANCEMENT DETAILS



				RP, LK	EA,MB, MC	MB	RIVER ISLAND SOUTH PRELIMINARY DESIGN		
Ē				DRAWN	DESIGNED	CHECKED		Motro	in 🔨
E				MC	JAN 2015	130235			501 Portug
i –	IO. BY	DATE	REVISION DESCRIPTION	APPROVED	DATE	PROJECT	CLACKAMAS COUNTY, OREGON		54 ave.

PILES

ALL VERTICAL PILES SHALL BE INSTALLED USING VIBRASONIC PILE DRIVING EQUIPMENT. INSTALLATION BY EXCAVATION OR HAMMERING WILL NOT BE ALLOWED.

RIGGING

RIGGING FOR PILE TESTING SHALL CONFORM TO THE TENSION SCALE MANUFACTURER'S RECOMMENDATIONS.

CHOKERS, CABLES AND SHACKLES SHALL HAVE MINIMUM WORKING LOAD RATING OF 12 TONS. FITTINGS SHALL BE SIZED ACCORDINGLY

TESTING

TESTING OF PILES SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER OR OTHER QUALIFIED PERSONNEL.

EACH PILE TEST SHALL HAVE UPWARD LOAD GRADUALLY INCREASED AND AS CLOSELY ALIGNED TO AXIS OF PILE AS POSSIBLE. RECORD THE PILE DIAMETER, EMBEDMENT DEPTH AND MAXIMUM FORCE REQUIRED TO MOVE THE PILE. UP TO A TOTAL OF THREE LOADINGS MAY BE REQUIRED AT EACH EMBEDMENT DEPTH.

PROOF TESTS SHALL BE MADE AT UP TO FOUR EMBEDMENT DEPTHS TO BE DETERMINED IN THE FIELD. AS A GUIDELINE TEST EMBEDMENT DEPTHS MAY INCLUDE 6', 8', 10', AND 12'.

EXCAVATOR CONDUCTING PULL OUT LOADING SHALL BE POSITIONED NO CLOSER THAN EMBEDMENT DEPTH OF PILE IF POSSIBLE. IF A CLOSER POSITIONING IS REQUIRED, EXCAVATOR SHALL BE NO CLOSER THAN THAT REQUIRED TO GENERATE DESIRED LOADING WITH DISTANCE FROM PILE NOTED IN THE TEST RECORD. LOAD MAY BE SPREAD IN THIS SITUATION BY POSITIONING THE EXCAVATOR ACROSS HORIZONTAL LOGS, WITH DISTANCE FROM PILE, LOG NUMBERS AND LENGTH NOTED IN THE TEST RECORD.

PULL OUT RESISTANCE READING SHALL BE COMPARED AGAINST EXCAVATOR MAX LIFT OFFSET TABLE.

10% OF PRODUCTION PILINGS SHALL BE PROOF TESTED. IF RESULTS VARY MORE THAN 50% THEN IT SHOULD BE ANTICIPATED THAT UP TO 25% OF THE PRODUCTION PILINGS SHALL BE PROOF TESTED. IF THE PILE EMBEDDMENT DEPTH DOES NOT MEET MINIMUM, OWNERS REPRESENTATIVE MAY REQUEST ADDITIONAL PULLOUT TESTING.

CONSTRUCTED DRIVEN PILE EMBEDMENT DEPTH SPECIFIED IN THE DRAWINGS MAY BE REDUCED OR INCREASED, PENDING PULL OUT TEST RESULTS, AT THE CONTRACTOR'S EXPENSE.



TYPICAL DETAILS





METRO REVEGETATION SPECIFICATIONS

														2016								T
		Scientific nome	Common nom		110:+ 2	llmit /		llnit C	1101+ 7					2016	Changes							
				2 04	3.2	1 01	3 33	2 96	2 28	0111 9		Scientific hai	Common name	Order	Needed	Unit 1	Unit 2	Unit 4		Unit 6	Unit /	Unit 9
TREES				2.04	5.2	1.01	5.55	2.50	2.20	0.7				Cuttings (26")		2.04	3.2	1.01	3.33	2.96	2.28	0.7
2016	Tree	Abies arandis	Grand Fir	100			100				CUTTINGS			Cuttings (50)					_			
2016	Tree	Alnus rubra	Red Alder			300		200			2016 Shrub	Salix fluviatilis	Columbia River Willow					600	0	1,500	500	-
2016	Tree	Fraxinus latifolia	Oregon Ash	100	200	500	300	200	300	300	2016 Shrub	Salix geyeriana	Geyer's Willow						_			
2016	Tree	Populus trichocarpa	Black Cottonwood	100	200	300	200	200	500	200	2016 Shrub	Salix hookeriana	Hooker's Willow									
2016	Tree	Psuedotsuga menziesii	Douglas Fir	200	400	500	200	200		200	2016 Shrub	Salix lasiandra	Pacific Willow							1,000	1,000	ł
2016	Tree	Quercus garryana	Oregon Oak	200	700			200			2016 Shrub	Salix piperi	Piper's Willow									_
2016	Tree	Rhamnus purshiana	Cascara		700						2016 Shrub	Salix rigida	Mackenzie's Willow									
2016	Tree	Thuja plicata	Western Red Cedar	200	,00		200		200		2016 Shrub	Salix scouleriana	Scouler Willow							1,000		
2016	Tree	Tsuaa heterophylla	Western Hemlock	100			200		200		2016 Shrub	Salix sessilifolia	Soft-Leaved Willow									
		Total Trees		700	2.000	600	1.000	800	700	500	2016 Shrub	Salix sitchensis	Sitka Willow					600	C	1,500	1,000	i -
SHRUB	s			700	2,000		1,000	000	700		2016 Cuttings Totals											
Since													•	·						•		
2016	Shrub	Acer circinatum	Vine Maple						200													
2016	Shrub	Amelanchier alnifolia	Serviceberry		400																	
2016	Shrub	Cornus sericea	Red Osier Dogwood	400	100		700	500	500	300												
2016	Shrub	Euonymus occidentalis	Western Wahoo	100																	CUT TOP SO	QUARE
2016	Shrub	Holodiscus discolor	Oceanspray		700			500												/ , I	ROM SPLI	TTING
2016	Shrub	Lonicera involucrata	Twinberry												OST TO SPECI	FIED						
2016	Shrub	Mahonia aquifolium	Tall Oregon Grape		700		300	500			BARE ROOT PLAN	\sim	YEYL	BASE (DF PLANT	RTU	DRIVE LIVI	E STAKES 2	/3			
2016	Shrub	Mahonia nervosa	Dull Oregon Grape										$\langle y \rangle \langle y $	/			INTO NAT	ive soil —		<u>_</u>	FINISH GRA	4DE
2016	Shrub	Oemleria cerasiformis	Indian Plum		300			200			WITH FINISH GR	ADE			ND SOIL TO FO RING WELL AT	RM OUTER						
2016	Shrub	Philadelphus lewisii	Mock Orange		400			300						EDGE	OF PLANTING	HOLE						
2016	Shrub	Physocarpus capitatus	Ninebark	400		300	600	500	500	300	EVENLY AROUNI	MITTIN .		ATT.								IV/E
2016	Shrub	Ribes sanguineum	Red flowering currant	t	300						DIRT MOUND -				E SOIL						STAKE W	ITH BUDS
2016	Shrub	Rosa nutkana	Nutka Rose		300			500			WIDTH OF			8 <u>4</u>							POINTING	3 UP
2016	Shrub	Rosa pisocarpa	Swamp Rose	200			400		300	300	PLANTING											
2016	Shrub	Rubus parviflorus	Thimbleberry		400			500														
2016	Shrub	Rubus spectabilis	Salmonberry						300		l						NATIVE SC				1	
2016	Shrub	Salix lasiandra	Pacific Willow				700				I			, 1 lee								
2016	Shrub	Salix sitchensis	Sitka Willow				800														- TRIM OF	F BRANCH
2016	Shrub	Sambucus cerulea	Blue Elderberry		400								ROOTS F	OR SUPPORT							WITH CLI	EAN CUTS
2016	Shrub	Sambucus racemosa	Red Elderberry				400										CUT E					
2016	Shrub	Spiraea douglasii	Spiraea	400	400	300	600	500	500	400							10 / 1	OINT				
2016	Shrub	Symphoriocarpus albus	Snowberry	200	700		500	1,000	300													
		SHRUB TOTAL		1,600	5,000	600	5,000	5,000	2,600	1,300		RARF	ROOT DETAIL					I\/F			ταιι	
														6	imin	ary						
		PLANT TOTAL		2,300	7,000	1,200	6,000		3,300	1,800			LALE	IPrei	1111111	tion	1	NUT	U JUALE			
														L. Fo	r Constr	UCTION	2					
														NOTIO								

DATE

REVISION DESCRIPTION

RIVER ISLAND SOUTH PRELIMINARY DESIGN METRO CLACKAMAS COUNTY, OREGON Metro

RP, LK	EA,MB, MC	MB
DRAWN	DESIGNED	CHECKED
MC	IAN 2015	120225
IVIC	JAN 2013	130233

