

- COVER, VICINITY MAP AND SHEET INDEX
- GENERAL NOTES AND ABBREVIATIONS
- GENERAL NOTES
- EROSION CONTROL GENERAL NOTES AND DETAILS
- **EROSION CONTROL DETAILS**
- EXISTING SITE, ACCESS, STAGING, ESC AND SURVEY CONTROL
- PROPOSED DESIGN AND SHEET KEY

- GOOSE CREEK PLAN AND PROFILE
- GOOSE CREEK SECTIONS 1+00 TO 6+00
- GOOSE CREEK SECTIONS 7+00 TO 15+00
- GOOSE CREEK SECTIONS 16+00 TO 22+00
- GOOSE CREEK SECTIONS 23+00 TO 26+00
- GOOSE CREEK SECTIONS 27+00 TO 29+00
- GOOSE CREEK CONNECTOR CHANNEL
- **RIVER ISLAND NORTH CUT-FILL PLAN**
- RIVER ISLAND NORTH PROPOSED ELEVATION BANDING
- **RIVER ISLAND NORTH PROFILES A-E**
- **RIVER ISLAND NORTH RIGHT BANK PLAN AND SECTIONS**
- PROPOSED RIVER ISLAND TERRACE SPILLWAY
- RIVER ISLAND NORTH BORROW AREA
- RIVER ISLAND NORTH BORROW AREA WITH ELEVATION BANDING

- TURTLE HABITAT ENHANCEMENT DETAILS
- RIGHT BANK DETAILS 1-2 AND BURIED LOG STRUCTURE DETAILS 3-4
- FLOOD PLAIN LARGE WOOD DETAIL 1
- PILE TESTING DETAIL 1 AND FULLY THREADED ROD DETAIL 2
- LARGE WOOD ENHANCEMENT CONFIGURATION DETAILS 1-3
- GOOSE CREEK FORD PLAN AND PROFILE A

- REVEGETATION

PERMIT SUBMITTAL

COVER, VICINITY MAP AND SHEET INDEX

G1 OF 29

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE OREGON STATE DEPARTMENT OF TRANSPORTATION (ODOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL.

ODFW IN-WATER WORK PERIODS

WORK SHALL OCCUR DURING THE ODFW PERMITTED IN-WATER WORK PERIOD: JULY 15-AUGUST 31 UNLESS OTHERWISE COORDINATED WITH ODFW AND APPROVED IN WRITING BY DSL.

EXISTING DATA

TOPOGRAPHIC DATA WAS COLLECTED BY INTER-FLUVE USING RTK AND TOTAL STATION IN DECEMBER 2013 AND FEBRUARY 2015. BATHYMETRIC DATA WAS COLLECTED BY INTER-FLUVE USING RTK AND SONAR IN JANUARY AND FEBRUARY OF 2014.

HORIZONTAL DATUM: STATE PLANE NAD83 OREGON NORTH VERTICAL DATUM: NAVD88

HYDRAULIC MODELING BY INTER-FLUVE USING USACE HEC-RAS (4.1.0). MODEL CALIBRATED USING SURVEYED WATER SURFACE ELEVATIONS AND EXISTING HIGH WATER MARKS.

GIS DATA INCLUDING: AERIAL PHOTOGRAPHY, LIDAR, FISH USE, SURFACE SOILS INFORMATION, LAND OWNERSHIP, AND TRANSPORTATION ROUTES PROVIDED BY METRO.

SOILS

SUBSURFACE SOILS ARE EXPECTED TO BE SAND, GRAVEL, COBBLES, AND BOULDERS. EXCAVATIONS BELOW THE SURFACE MAY ENCOUNTER SANDY RIVER MUDSTONE AT SHALLOW DEPTHS. MUDSTONE SHALL BE KEPT SEPARATE FROM RIVER GRAVELS AND NOT USED FOR BACKFILL OF LARGE WOOD STRUCTURES. VOLUME OF NON-NATIVE MATERIALS (E.G. ASPHALT, RIPRAP) ARE BASED ON SURVEY AND VISUAL ESTIMATES. CONTRACTOR SHALL CONDUCT OWN INVESTIGATIONS IF ADDITIONAL DATA IS REQUIRED AT NO ADDITIONAL COST TO OWNER.

UTILITIES

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

THE CONTRACTOR SHALL CALL (800-322-2344) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION.

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.

THE CONTRACTOR SHALL PROVIDE EQUIPMENT AND LABOR TO AID THE EFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO ADDITIONAL COST TO OWNER.

CONSTRUCTION STAKING

OWNER'S REPRESENTATIVE WILL PROVIDE STAKING OF PROJECT LIMITS, GRADE STAKES, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.

CONTRACTOR SHALL MEET WITH THE OWNER AND OWNER'S REPRESENTATIVE TO DEFINE AND MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF EQUIPMENT OR MATERIALS ONTO THE SITE.

THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST TO THE OWNER.

CONSTRUCTION MATERIALS

CONTRACTOR SHALL ALLOW FOR EXPANSION OF EXCAVATED MATERIAL AND COMPACTION OF PLACED MATERIAL AT NO ADDITIONAL MEASURE OR COST TO THE OWNER. MEASUREMENT AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE WITHOUT PRIOR WRITTEN APPROVAL.

LOCATION, ALIGNMENT, AND ELEVATION OF LOGS AND LOGS WITH ROOTWADS ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS AND MATERIAL SIZE.

THE CONTRACTOR WILL DISPOSE OF NON-NATIVE MATERIAL ENCOUNTERED IN AN APPROVED, LEGAL OFFSITE DISPOSAL FACILITY.

CONSTRUCTION ACCESS/TRAFFIC CONTROL

CONTRACTOR SHALL SUBMIT AN ACCESS, STAGING, AND STOCKPILE PLAN TO OWNER FOR APPROVAL PRIOR TO MOBILIZATION.

PUBLIC ACCESS TO/ALONG ROADWAYS AND THROUGH BARTON PARK SHALL BE MAINTAINED AT ALL TIMES.

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR OBTAINING ANY REQUIRED TRAFFIC CONTROL OR ACCESS PERMITS.

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR PROVIDING ANY REQUIRED TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO, SIGNAGE AND FLAGGERS.

THE CONTRACTOR SHALL PLACE SIGNAGE UPSTREAM OF WORK AREA IN A MANNER TO DISCOURAGE RIVER USERS FROM ENTERING THE WORK AREA.

ALL SAPLINGS AND TREES TO BE TRANSPLANTED OR REMOVED SHALL BE CLEARLY MARKED AND APPROVED BY METRO.

ALL EQUIPMENT, MATERIALS, AND PERSONNEL SHALL REMAIN WITHIN THE LIMITS OF DISTURBANCE.

THE CONTRACTOR SHALL KEEP THE WORK AREAS IN NEAT CONDITION, FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.

CONTRACTOR SHALL IMPLEMENT MEASURES TO CONTROL AND MINIMIZE WIND BLOWN DUST FROM THE SITE.

ALL DISTURBED AREAS INCLUDING ROADS, DRIVEWAYS AND ACCESS ROUTES SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AND RE-VEGETATED PER PLANS.

ALL DISTURBED AREAS OUTSIDE THE LIMITS OF DISTURBANCE SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AT NO ADDITIONAL COST TO THE OWNER.

EROSION CONTROL

CONTRACTOR SHALL BE SOLELY RESPONSIBLE AT OWN EXPENSE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION CONTROL REGULATIONS AND TO MAINTAIN CLEAN ACCESS ROUTES.

FISH RESCUE

ALL FISH RESCUE EFFORTS SHALL BE SUPERVISED BY THE OWNER'S REPRESENTATIVE AND SHALL BE PERFORMED BY PERSONNEL EXPERIENCED WITH THE COLLECTION AND HANDLING OF SALMONIDS FROM CONSTRUCTION SITES.

ALL FISH TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA WILL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUME OF FRESH RIVER WATER.

CAPTURED FISH SHALL BE IMMEDIATELY RELEASED INTO THE RIVER AT AREAS SELECTED BY EXPERIENCED PERSONNEL. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AN ODFW/NMFS SCIENTIFIC TAKE PERMIT.

WETLANDS AND WATERS OF THE US

THE ORDINARY HIGH WATER (CLACKAMAS OHW) OR APPROXIMATE LOW WATER LINES DISPLAYED IN THIS DESIGN PACKAGE WERE DELINEATED BY INTER-FLUVE STAFF IN 2013 AND 2014. THE WETLAND BOUNDARIES WERE DELINEATED IN 2015. CLACKAMAS OHW AND WETLAND BOUNDARIES ARE BASED UPON ANALYSIS, MODELING, AND BEST PROFESSIONAL JUDGEMENT.

THE CLACKAMAS OHW AND WETLAND LINES DO NOT REPRESENT JURISDICTIONAL BOUNDARIES. WITHIN THE STATE OF OREGON. THE ARMY CORPS OF ENGINEERS AND THE DEPARTMENT OF STATE LANDS HAVE THE FINAL AUTHORITY IN DETERMINING WATERS AND WETLANDS BOUNDARIES AND REGULATIONS.

ABBREVIATIONS

BMPs	BEST MANAGE
CY	CUBIC YARDS
DBH	DIAMETER AT E
DIA	DIAMETER
A	EACH
T	FOOT
TR	FULLY THREAD
IORIZ	HORIZONTAL
NTS	NOT TO SCALE
٧	NORTH
.B	POUND
W	LARGE WOOD
VAX	MAXIMUM
ИIN	MINIMUM
DDFW	OREGON DEPA
RD	ROAD
ГҮР	TYPICAL
/ERT	VERTICAL
ЭНW	ORDINARY HIG
.F	LINEAR FEET
AC	ACRE

				IK RP SM	FA MM	IK
				DRAWN	DESIGNED	CHECKED
				N 4 N 4	ALLC 2015	120225
				IVIIVI	AUG 2015	130235
				APPROVED	DATE	PROJECT
NO.	BY	DATE	REVISION DESCRIPTION			
			•			

RIVER ISLAND NORTH PRELIMINARY DESIGN METRO CLACKAMAS COUNTY, OREGON



inter fluve

BEST MANAGEMENT PRACTICES

BREAST HEIGHT

ED ROD

ARTMENT OF FISH AND WILDLIFE

GH WATER



PERMIT SUBMITTAI

GENERAL NOTES AND ABBREVIATIONS

G2 OF 29

TURTLE CROSSING BEST MANAGEMENT PRACTICES

ALL WORK SHALL CONFORM TO THE BELOW LIST OF OREGON DEPARTMENT FISH AND WILDLIFE (ODFW) TURTLE BEST MANAGEMENT PRACTICES TO THE EXTENT PRACTICABLE. THE CONTRACTOR SHALL WORK WITH THE OWNER'S REPRESENTATIVE TO PROTECT TURTLES AND TURTLE HABITAT THROUGHOUT THE CONSTRUCTION PROCESS.

CONTRACTOR SHALL:

MINIMIZE TEMPORARY CHANGES TO THE HYDROLOGY OR SEDIMENTATION RATES OF WATERBODIES SUPPORTING TURTLES FROM GROUND DISTURBANCES WITHIN 500 FT (150 M) OF NATIVE TURTLE HABITAT, OR WITHIN 150 FEET OF WATERWAYS THAT FLOW TO NATIVE TURTLE HABITAT:

- A. PROPERLY INSTALL SILT FENCING AROUND WORK AREAS, WITH REGULAR INSPECTION AND MAINTENANCE;
- B. USE JUTE MATTING, WEED-FREE NATIVE STRAW, MULCH BERMS, OR OTHER NATURAL FIBER EROSION CONTROL PRODUCTS ON DISTURBED AREAS IMMEDIATELY AFTER PROJECT COMPLETION TO MINIMIZE EROSION; DO NOT USE PRODUCTS WITH PLASTIC MESH THAT CAN ENTANGLE WILDLIFE; AND
- C. PROMPTLY RE-VEGETATE AREAS OF TEMPORARY DISTURBANCE WITH NATIVE SPECIES.

MARK CONFIRMED TURTLE NESTS WITH TEMPORARY FLAGGING, SURROUNDING WITH SILT FENCE, ETC. TO PROTECT FROM DISTURBANCE (E.G., CRUSHING BY HEAVY EQUIPMENT). TEMPORARY NEST MARKERS / BARRICADES SHOULD BE REMOVED AS SOON AS POSSIBLE AFTER THE PROJECT IS COMPLETE TO MINIMIZE POSSIBLE ATTRACTION OF PREDATORS.

AVOID INJURING OR DISTURBING NATIVE TURTLES DURING CONSTRUCTION ACTIVITIES IN OR NEAR OCCUPIED HABITAT:

A. HAVE WORK AREAS INSPECTED BY A QUALIFIED BIOLOGIST EXPERIENCED WITH TURTLES BEFORE AND DURING CONSTRUCTION;
 B. SEASONALLY RESTRICT CERTAIN ACTIVITIES KNOWN TO IMPACT TURTLE HABITAT TO THE EXTENT PRACTICABLE

KEEP ACCESS TO DESIGNATED WORK PATHS TO AND FROM THE STAGING AREA AND WORK SITE(S) TO REDUCE UNNECESSARY HUMAN ACTIVITY AND GROUND DISTURBANCE TO THE TURTLES WITHIN PROJECT SITE. MINIMIZE THE NUMBER OF ACCESS WAYS TO THE EXTENT PRACTICABLE.

LOCATE PROJECT STAGING AREAS AND OTHER CONSTRUCTION RELATED SUPPORT FEATURES (E.G., CONCRETE TRUCK WASHOUT AREA, AND EQUIPMENT FUELING STATIONS) AT LEAST 165 FT (50 M) FROM WATERBODIES AND SUITABLE TURTLE NESTING HABITAT. IF THESE AREAS CANNOT BE LOCATED OUTSIDE THESE BOUNDARIES, INSTALL SILT FENCING IN ROAD CONSTRUCTION AREAS TO PREVENT TURTLES, INCLUDING NESTING TURTLES, FROM ENTERING THE WORK ZONE. CONSIDER TURTLE ACTIVITY CYCLE IN TIMING OF SILT FENCE INSTALLATION. BURY SILT FENCE INTO GROUND AT A 4 IN (10 CM) DEPTH TO PREVENT TURTLES FROM MOVING UNDER FENCE. MONITOR REGULARLY. REMOVE FENCING AS SOON AS PRACTICABLE AFTER WORK IS COMPLETE.

IF SMALL ENGINE EQUIPMENT SUCH AS PUMPS FOR TEMPORARY WATER MANAGEMENT MUST BE USED WITHIN 165 FT (50 M) OF A WATERBODY OF KNOWN OR SUSPECTED TURTLE NEST SITES, PLACE IN A LEAK-PROOF CONTAINER TO CONTAIN SPILLS FROM BROKEN FUEL LINES OR ACCIDENTAL SPILLS DURING REFUELING.

TURTLE EXCLUSION FENCE DESIGNS

TURTLE EXCLUSION FENCING SHOULD BE CONSTRUCTED OF 2" SQUARE WELDED OR WOVEN MESH WIRE 16 - 12.5 GAUGE. FENCE SHALL BE BURIED A MINIMUM OF 6" UNDER THE SOIL, WITH A MINIMUM OF 18" ABOVE GROUND. OWNER SHALL MARK AREAS THAT REQUIRE FENCING.

LIVE TREES

ALL TREES NOT MARKED FOR REMOVAL SHALL BE LEFT STANDING UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT DEBARK OR DAMAGE LIVE TREES.

KEEP HEAVY EQUIPMENT OUT OF CANOPY DRIP LINE OF EXISTING TREES TO REMAIN.

JURISDICTIONAL AREA IMPACTS:

				Fill V	olume
			Fi	ll Dimens	ions ¹
Wetland/Waterbody Name	Length	Width (ft)	Depth (ft)	Area	
	(ft)	Widen (it)		(sq. ft.)	
Clackamas River - Goose Creek Area	1500	115	3.02	172,331	19,251
Clackamas River - River Island North Area	1500	403	6.55	604,004	146,560
Clackamas River - Right Borrow Area	675	154	3.73	104,052	14,37

Notes:

¹ Fill dimensions represent the summation of discontinguous areas.

² Work duration estimate equals 60 days.

			ŀ	Remova	al Volui		
Wetland/Waterbody Name	Removal Dimensions						
Wetland/Waterbody Name	Length (ft)	Width (ft)	Depth (ft)	Area (sq. ft.)			
Clackamas River - Goose Creek Area	2700	140	4.67	377,665	65,315		
Clackamas River - River Island North Area	1700	186	3.50	616,656	79,875		
Clackamas River - Right Borrow Area	900	206	4.82	185,692	33,1		
Notes:							

Removal dimensions represent the summation of discontinguous areas.

Work duration estimate equals 60 days.

TREE SALVAGE

ALL TREES AND SLASH REMOVED FOR CONSTRUCTION SHALL BE TEMPORARILY STOCKPILED WITHIN LIMITS OF DISTURBANCE. STOCKPILED TREE/SLASH SHALL BE REINCORPORATED INTO FINISHED PROJECT.

ANY REMOVED VEGETATION GREATER THAN 6 INCHES DIAMETER, AT BASE, AND 15 FEET LONG SHALL BE INCORPORATED INTO LOG STRUCTURES. CONTRACTOR IS RESPONSIBLE FOR REMOVING SMALLER CLEARING AND GRUBBING DEBRIS FROM THE SITE AND DISPOSING AT A LEGAL LOCATION AT THE END OF THE PROJECT UNLESS DIRECTED BY THE OWNER'S REPRESENTATIVE.

ALL TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOT WAD AND UTILIZED IN THE STREAM CONSTRUCTION AS DIRECTED BY OWNER'S REPRESENTATIVE.

ALL NATIVE MATERIAL SLASH SHALL BE STOCKPILED TO BE INCORPORATED INTO THE FINISHED PROJECT.

õ									
2					ΕΔ ΜΜ	IK	RIVER ISLAND NORTH PRELIMINARY DESIGN		
ñ				DRAWN	DESIGNED	CHECKED			interflu
Ž				ММ	AUG 2015	130235	INIE I RO	Vietro	SOI Partney Avenue S
	NO. B	Y DATE	REVISION DESCRIPTION	APPROVED	DATE	PROJECT	CLACKAMAS COUNTY, OREGON		Hood River, OR 974 541.388.9003 www.interfluve.com
							· · · · · · · · · · · · · · · · · · ·	4	



EROSION/SEDIMENTATION CONTROL (ESC) PLAN

THE EROSION AND SEDIMENT CONTROL (ESC) PLAN PROVIDED IS FOR INFORMATIONAL PURPOSES ONLY, THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION CONTROL MEASURES TO COMPLY WITH APPLICABLE REGULATIONS.

THE RECOMMENDATIONS FOR AN ESC PLAN INCLUDED HEREIN WILL PROVIDE A GUIDELINE FOR THE CONTRACTOR TO DEVELOP AND IMPLEMENT AN ESC PLAN.

- Α. THE IMPLEMENTATION OF AN ESC PLAN AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE Β. CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- ESC FACILITIES AS APPROXIMATELY SHOWN ON THIS PLAN ARE TO BE C CONSTRUCTED PRIOR TO CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT ENTER SURFACE WATERS, THE DRAINAGE SYSTEM, OR VIOLATE APPLICABLE WATER STANDARDS.
- THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS D. FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST TO OWNER FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
- G. STABILIZED CONSTRUCTION ENTRANCES AND ADDITIONAL MEASURES MAY BE REQUIRED AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT TO ENSURE ALL ACCESS ROADS ARE KEPT CLEAN AT NO ADDITIONAL COST TO OWNER.

INSPECTION AND MAINTENANCE

ALL ESC FACILITIES SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL ESC FACILITIES SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD AND AFTER EVENTS **EXCEEDING 2 HOURS DURATION.**

CONTRACTOR'S ESC RECORD

WEEKLY REPORTS SUMMARIZING THE SCOPE OF INSPECTIONS, THE PERSONNEL CONDUCTING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN, AND ACTIONS TAKEN AS A RESULT OF THESE INSPECTIONS SHALL BE PREPARED AND RETAINED ON SITE BY THE CONTRACTOR. IN ADDITION, A RECORD OF THE FOLLOWING DATES SHALL BE INCLUDED IN THE REPORTS

- 1. WHEN MAJOR GRADING ACTIVITIES OCCUR.
- 2. DATES OF RAINFALL EVENTS EITHER EXCEEDING 2 HOURS DURATION OR MORE THAN 0.5 INCHES/24 HOURS.

- WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON 3. SITE, OR ON A PORTION OF THE SITE.
- 4. WHEN STABILIZATION MEASURES ARE INITIATED FOR PORTIONS OF THE SITE.
- 5. ESC RECORDS SHALL BE MADE AVAILABLE TO THE OWNER AND OWNER'S REPRESENTATIVE ON REQUEST AND SHALL BE PROVIDED FOR REVIEW AND APPROVAL PRIOR TO APPLICATION FOR PAYMENT.

STABILIZE SOILS AND PROTECT SLOPES

FROM MAY 1 THROUGH SEPTEMBER 30, ALL EXPOSED SOILS SHALL BE PROTECTED FROM EROSION BY MULCHING, HYDROSEED COVERING, OR OTHER APPROVED MEASURES WITHIN THREE DAYS OF GRADING. FROM OCTOBER 1 THROUGH APRIL 30, ALL EXPOSED SOILS MUST BE PROTECTED WITHIN 2 DAYS OF GRADING. SOILS SHALL BE STABILIZED BEFORE A WORK SHUTDOWN, HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST. SOIL STOCKPILES MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES.

DESIGN, CONSTRUCT, AND PHASE CUT AND FILL SLOPES IN A MANNER THAT WILL MINIMIZE EROSION. REDUCE SLOPE VELOCITIES ON DISTURBED SLOPES BY PROVIDING TEMPORARY BARRIERS. STORMWATER FROM OFF SITE SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON SITE.

AFTER FINAL SITE STABILIZATION

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BEST MANAGEMENT PRACTICES (BMPs) ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED FROM THE SITE OR INCORPORATED INTO FINISHED GRADING. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED.

RIVER DIVERSION

DIVERSION MAY BYPASS THE RIVER AROUND SMALLER WORK AREAS AT CONTRACTOR'S DISCRETION.

DEWATERING OF IN-CHANNEL WORK AREA(S) SHALL OCCUR CONCURRENT WITH FISH RESCUE. CONTRACTOR SHALL COORDINATE WITH OWNER FOR FISH RESCUE. CONTRACTOR SHALL PROVIDE OWNER AMPLE TIME TO SCHEDULE FISH RESCUE. IF DIVERSION FAILS DUE TO CONTRACTOR NEGLIGENCE, FISH RESCUE SHALL BE REPEATED BY OWNER'S REPRESENTATIVE AT CONTRACTOR'S EXPENSE.

IF ADDITIONAL PUMPING IS REQUIRED TO DEWATER DURING CONSTRUCTION. PUMPED DISCHARGE SHALL RELEASE SEDIMENT-LADEN WATER AT AN UPLAND DISCHARGE LOCATION IN A MANNER THAT DOES NOT CAUSE EROSION, CONTAMINATION OR INCREASE TURBIDITY OF SURFACE WATERS (SEE CONSTRUCTION DEWATERING).

OWNER'S REPRESENTATIVE SHALL APPROVE DEWATERING DISCHARGE LOCATION PRIOR TO IMPLEMENTATION.

CONSTRUCTION DEWATERING

CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO AVOID THE RELEASE OF SEDIMENT-LADEN WATER TO SURFACE WATERS. SEDIMENT LADEN WATER MAY BE PUMPED TO AN UPLAND DISCHARGE LOCATION AND ALLOWED TO SHEET FLOW THROUGH EXISTING VEGETATION BEFORE INFILTRATING INTO THE GROUND. IF THIS METHOD IS NOT SUFFICIENT TO PREVENT RETURN OF TURBID WATER TO THE RIVER, A 'DIRT-BAG' OR SEDIMENT RETENTION STRUCTURE MAY BE REQUIRED AS NECESSARY TO COMPLY WITH LAWS AND PERMIT REQUIREMENTS AT NO ADDITIONAL COST TO THE OWNER.

CONTRACTOR SHALL PROVIDE PLASTIC SHEETING OR GEOTEXTILE LINER OR PLYWOOD OR METAL PLATING AS NECESSARY TO DISSIPATE PUMP DISCHARGE JET TO PREVENT EROSION.

SPILL POLLUTION PREVENTION PLAN

THE CONTRACTOR SHALL PREPARE AND IMPLEMENT A, PROJECT-SPECIFIC, SPILL PREVENTION, CONTROL, AND COUNTERMEASURES PLAN (SPCC PLAN) FOR THE DURATION OF THE PROJECT. THE CONTRACTOR SHALL SUBMIT THE PLAN TO THE PROJECT ENGINEER NO LATER THAN THE DATE OF THE PRECONSTRUCTION CONFERENCE.

ON-SITE CONSTRUCTION ACTIVITIES MAY COMMENCE UNTIL THE CONTRACTING AGENCY ACCEPTS AN SPCC PLAN FOR THE PROJECT.

EROSION CONTROL SEED MIX:

SEED MIX SPECIFICATION

Scientific name	Common name	% of	Mix
Deshampsia elongata ¹	Slender hairgrass		60
Agrostis exarata ¹	Spike bentrgrass		30
Prunella vulgaris ¹		10	
¹ NATIVE WILLAMETTE VA	LLEY SEED STOCK		

SEED MIX APPLICATION

APPLY AT 14LB/ACRE. PRIOR TO DISTRIBUTION, MIX SEED WITH 50:50 CRACKED CORN TO FACILITATE EVEN DISTRIBUTION IN LIMITS OF DISTURBANCE ABOVE CLACKAMAS OHW.

DRAWN DESIGNED CHECKED MM AUG 2015 130235			LK,RP,SM	EA,MM	JK	RIVER ISLAND
MM AUG 2015 130235			DRAWN	DESIGNED	CHECKED	
			MM	AUG 2015	130235	
APPROVED DATE PROJECT CLACK			APPROVED	DATE	PROJECT	
BY DATE REVISION DESCRIPTION CLACK	BY DATE	TE REVISION DESCRIPTION				CLACKA

NORTH PRELIMINARY DESIGN METRO MAS COUNTY, OREGON





PERMIT SUBMITTAL

EROSION CONTROL GENERAL NOTES AND DETAILS

G4 ^{oF} 29







- 1. THE SILT FENCE SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, SILT FENCE SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND BOTH ENDS SECURELY FASTENED TO THE POST. ALTERNATIVELY, OVERLAP AND INTERLOCK TWO POSTS WITH ATTACHED FABRIC AS REQUIRED TO MEET APPLICABLE REGULATIONS.
- 2. THE SILT FENCE IS TO BE INSTALLED AT LOCATIONS SHOWN ON THE PLAN ALONG THE DOWNHILL PERIMETER OF CONSTRUCTION AREAS. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24 INCHES.
- 3. THE SILT FENCE SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6 INCHES. ALL EXCAVATED MATERIAL FROM SILT FENCE INSTALLATION SHALL BE BACK-FILLED AND COMPACTED ALONG THE ENTIRE DISTURBED AREA.
- 4. STANDARD OR HEAVY DUTY SILT FENCE SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2 INCHES X 2 INCHES POST INSTALLATION.
- 5. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED, OR AS DIRECTED BY OWNER'S REPRESENTATIVE.







BE REPEATED AT CONTRACTOR'S EXPENSE.

ADDITIONAL COST TO THE OWNER.

WORK AREAS.





<i>^</i>	IK	
	IK	

	LK,RP,SM	EA,MM	JK	RIVER ISLAND NORTH PRELIMINARY DESIGN
	DRAWN	DESIGNED	CHECKED	METDO
	MM	AUG 2015	130235	IVIETRO
	APPROVED	DATE	PROJECT	
REVISION DESCRIPTION				CLACKANIAS COUNTY, ONE GOIN



		0	1 DZ		600
			300		600
			SCALE IN FEET		
ANT		LEGEN	ID		
A. A.		TEM	PORARY CONS	TRUCTION	STAGING
		EXIS (1 FT	FING CONTOUF . INTERVALS)	RS	
ANA MAN	METR	D PROI	PERTY LINES		
	——онж	ORD	INARY HIGH W	ATER	
1 Bas	x	-× SILT	FENCE, SEE	$\frac{1}{35}$	
	<u> </u>	EXIS	ring high flo	W CHANNE	EL
		LIMI	T OF DISTURBA	NCE	
		🔉 SURV	EY BENCHMA	₹К	
OHN	REBAR ·				
4		EXIS	FING LEVEE TO	BE REMOV	/ED
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		EXIS	FING WETLAND	)	
		2014	LOW WATER		
<u></u>		PRES	ERVATION ARE	A	
Ser ?	онш-онш-	ORD	INARY HIGH W	ATER (CLA	CKAMAS OHW)
in the second	NOTES:				
IG	1. NAT THE 30-A	URAL COLOR C PORTLAND M UGUST 11, 20	ORTHO-RECTIFI ETROPOLITAN / 14.	ED AERIAL AREA COLL	IMAGERY FOR ECTED JULY
	2. EXIS ON S TOP BASI	TING CONTOU SITE SURVEYS ( OGRAPHY WIT ED ON ON SITE	RS DERIVED FR CONDUCTED BY HIN THE AREA SURVEY DATA	OM LIDAR ( INTER-FLI OF DISTUR . LIDAR DA	DATA AND JVE, INC. BANCE IS ATA
	TOP	OGRAPHY OUT	ISIDE OF THE A	REA OF DIS	STURBANCE.
	3. PRO	PERTY LINES A	RE APPROXIMA	ATE.	
$\mathbf{\hat{\lambda}}$	4. MET YEAI	RO MAINTENA R VEGETATION	ANCE TO BE 2 - MAINTENANC	SEASON A	CCESS FOR 4 -
VG	SELEC	TED SUR	VEY BENC		RKS
	Point #	Northing	Easting	Elevation	Description
	30000028	628619.094	714299.481	195.435	REBAR
	30000051	628507.282	714333.521	192.740	REBAR
	30000500	629610.747	/13134.826	184.631	BW 200
hund		Pre	limir	hary	<b>y</b>

Not for Construction



EXISTING SITE, ACCESS, STAGING, ESC AND SURVEY CONTROL

G6 OF 29

























LOWER	UPPER	COLOR	LOWER	UPPER	COLOR							
154	157		165	166								
157	158		166	167								
158	159		167	168								
159	160		168	169								
160	161		169	170								
161	162		170	171								
162	163		171	172								
163	164		172	173								
164	165		173	194								
LEGEND ORDINARY HIGH WATER												
OHW		– EXIS (1 FT	ING CONT	JUKS _S)								
		PROF (1 FT	Posed Con . Interval	ITOURS _S)								
MHO	氟	BURI	ED LOG ST	RUCTURE	3 D2							
min	-	FLOC	)D PLAIN R	OUGHNES	$3S \begin{pmatrix} 1 \\ D3 \end{pmatrix}$							
NG ALCOV PRESERVE	ED											
P	ERN		SUB	MIT	TAL							
RIVER I	SLAN	) NOR	ТН	9	НЕЕТ							
ROPOS		EVATI	ON	E9	of <b>29</b>							
	154 157 158 159 160 161 162 163 164	154 137 157 158 159 160 160 161 161 162 162 163 163 164 164 165 000 000 000 000 000 000 000 0	154       157       158         157       158       159         159       160       161         161       162       163         163       164       164         164       165       0         0HW       0HW       0HW         0HW       0HW       0HW	154       157       158       166         157       158       166         158       159       167         159       160       168         160       161       169         161       162       170         162       163       171         163       164       172         164       165       173         CRECEND         ORDINARY HIGH         EXISTING CONT         (1 FT. INTERVAL         PROPOSED CON         (1 FT. INTERVAL         (1 FT. INTERVAL	154       157       158       103       100         157       158       166       167       168         159       160       168       169       160         160       161       169       170       171         161       162       170       171       172         163       164       172       173       194         LEGEND         ORDINARY HIGH WATER         EXISTING CONTOURS (1 FT. INTERVALS)         PROPOSED CONTOURS (1 FT. INTERVALS)         PREMIT SUBMIT         NING ALCOVE         PREMIT SUBMIT							

400 ELEVATION BANDS (FEET) ELEVATION BANDS (FEET)









1111 1111 1111			PROP	OSED CUT	OR FILL					
		CUT/ FILL	LOWER ∆ GROUND (FT)	HIGHER Δ GROUND (FT)	COLOR	VOLUME (CU. YDS)				
			-23	-20		2				
		YDS	-20	-15		310				
		3,18	-10		7,601					
```		(1)	-5	0		21,441				
			0	5		11,015				
		-ILL 1,374	5	10		2,931				
		14	10	14		428				
		0		80 SCALE IN FE	ET	160				
1 T		—онw—		D NARY HIGH	WATER	fat				
		UTW-	EVICT							
	<hr/>		(1 FT.	ING CONTO	)					
	PROPOSED CONTOURS (1 FT. INTERVALS)									
				OF DISTUR	BANCE					
xx-		x	— SILT F	ENCE						
CL1						Dru				
liminary										
		re	or Con	structi	on					
		۲Ŀ	KIVII	1-50	RIV	I I AL				
ve	RIVE	R IS	LAND N	ORTH		SHEET				
te 101 31	В	OKK	UW AR	ΕA		CT2 0L 7A				





GROUND SUBSTRATE					
	% OF TOTAL MIX				
	25 OR LESS				
	25				
	25-50				
	25 OR LESS				

1. TURTLE NESTING AREAS TO BE CONSTRUCTED USING TURTLE NESTING GROUND SUBSTRATE MIX 30 CUBIC YARDS PER NESTING AREA.

2. DEPOSIT GROUND SUBSTRATE IN MOUNDS MEASURING AT LEAST 20 FT X 20

TURTLE AREA BRUSH PILES TO BE COMPOSED OF NATIVE SLASH SMALLER THAN 12" DBH. BRUSH PILES TO BE A MINIMUM OF 10 FEET LONG X 10 FEET

# PERMIT SUBMITTAL

**TURTLE HABITAT** ENHANCEMENT DETAILS

D1 OF 29





# PERMIT SUBMITTAL

FLOOD PLAIN LARGE WOOD

D3 OF 29



#### VERTICAL LOGS

ALL VERTICAL LOGS SHALL BE INSTALLED USING VIBRASONIC PILE DRIVING EQUIPMENT. INSTALLATION BY EXCAVATION OR HAMMERING WILL NOT BE ALLOWED.

#### RIGGING

RIGGING FOR VERTICAL LOG TESTING SHALL CONFORM TO THE TENSION SCALE MANUFACTURER'S RECOMMENDATIONS.

CHOKERS, CABLES AND SHACKLES SHALL HAVE MINIMUM WORKING LOAD RATING OF 12 TONS. FITTINGS SHALL BE SIZED ACCORDINGLY

#### TESTING

TESTING OF VERTICAL LOGS SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER OR OTHER QUALIFIED PERSONNEL.

EACH VERTICAL LOG TEST SHALL HAVE UPWARD LOAD GRADUALLY INCREASED AND AS CLOSELY ALIGNED TO AXIS OF VERTICAL LOG AS POSSIBLE. RECORD THE VERTICAL LOG DIAMETER, EMBEDMENT DEPTH AND MAXIMUM FORCE REQUIRED TO MOVE THE VERTICAL LOG. UP TO A TOTAL OF THREE LOADINGS MAY BE REQUIRED AT EACH EMBEDMENT DEPTH.

PROOF TESTS SHALL BE MADE AT UP TO FOUR EMBEDMENT DEPTHS TO BE DETERMINED IN THE FIELD. AS A GUIDELINE TEST EMBEDMENT DEPTHS MAY INCLUDE 6', 8', 10', AND 12'.

EXCAVATOR CONDUCTING PULL OUT LOADING SHALL BE POSITIONED NO CLOSER THAN EMBEDMENT DEPTH OF VERTICAL LOG IF POSSIBLE. IF A CLOSER POSITIONING IS REQUIRED, EXCAVATOR SHALL BE NO CLOSER THAN THAT REQUIRED TO GENERATE DESIRED LOADING WITH DISTANCE FROM VERTICAL LOG NOTED IN THE TEST RECORD. LOAD MAY BE SPREAD IN THIS SITUATION BY POSITIONING THE EXCAVATOR ACROSS HORIZONTAL LOGS, WITH DISTANCE FROM VERTICAL LOG, LOG NUMBERS AND LENGTH NOTED IN THE TEST RECORD.

PULL OUT RESISTANCE READING SHALL BE COMPARED AGAINST EXCAVATOR MAX LIFT OFFSET TABLE.

10% OF PRODUCTION PILINGS SHALL BE PROOF TESTED. IF RESULTS VARY MORE THAN 50% THEN IT SHOULD BE ANTICIPATED THAT UP TO 25% OF THE PRODUCTION PILINGS SHALL BE PROOF TESTED. IF THE VERTICAL LOG EMBEDDMENT DEPTH DOES NOT MEET MINIMUM, OWNER'S REPRESENTATIVE MAY REQUEST ADDITIONAL PULLOUT TESTING.

CONSTRUCTED DRIVEN VERTICAL LOG EMBEDMENT DEPTH SPECIFIED IN THE DRAWINGS MAY BE REDUCED OR INCREASED, PENDING PULL OUT TEST RESULTS, AT THE CONTRACTOR'S EXPENSE.







0										
Š.									1	
-					IK RP SM	FA MM	IK	RIVER ISLAND NORTH PRELIMINARY DESIGN		
ب										
m					DRAWN	DESIGNED	CHECKED	NAETDO		🔨 intenfluxio
Ξ								IVIETR()	$\mathbf{M}$	< Under 3 fin we
<					MM	AUG 2015	130235	MEINO		501 Portugu Augura Sulla 10
ý										Hood River, OR 97031
·.					APPROVED	DATE	PROJECT		$\smile$	847.386.9003
_	NO.	BY	DATE	REVISION DESCRIPTION				CLACKAWAS COONTY, ONEOON	1	



# **PERMIT SUBMITTAI**

PILE TESTING DETAIL 1 AND FULLY THREADED ROD DETAIL 2

D4 OF 29



SHEET D5 OF 29

# PERMIT SUBMITTAL







0	300 600
	SCALE IN FEET
	LEGEND
	VEGETATIVE UNIT #1 (6.38 ACRES)
	VEGETATIVE UNIT #2 (6.25 ACRES)
	VEGETATIVE UNIT #3 (14.56 ACRES)
	VEGETATIVE UNIT #4 (6.58 ACRES)
	VEGETATIVE UNIT #5 (6.65 ACRES)

#### NOTE:

- 1. 1. SPECIES MIX TO VARY BY PLANTING UNIT. PLANTING WILL BE BY BARE ROOT AND CUTTINGS, 12-18" NATIVE STOCK, NATIVE WILLAMETTE VALLEY SEED STOCK TO BE PLANTED BY PROFESSIONAL REFORESTATION CONTRACTOR.
- 2. 2. REVEGETATION AREAS AND SPECIFICATIONS DEVELOPED BY METRO STAFF.
- 3. 3. REVEGETATION TO OCCUR ONLY ABOVE CLACKAMAS OHW.
- 4. SEE SHEET V2 FOR REVEGETATION SPECIES COMPOSITION.



## **PERMIT SUBMITTAL** SHEET

**REVEGETATION UNITS** 

V1 OF 29



LK, RP, SM

мм

APPROVED

EA,MM

DESIGNED

DATE

AUG 2015

JK

CHECKED

130235

PROJECT

Scientific name	Common name	Total	Unit 1	Unit 2	Unit 3	Unit 4	Unit 5
Abies grandis	Grand Fir	2,550	500	200	1500		350
Aln <mark>u</mark> s rubra	Red Alder	7,200	800	200	3500	1200	1,500
Cr <b>a</b> taegus douglasii	Black Hawthorn	2,000	1000	500		500	
Fraxinus latifolia	Oregon Ash	9,600	4500	2500	1000	1600	
Populus trichocarpa	Black Cottonwood	7,600	3,000	2,000	500	1,600	500
Psuedotsuga menziesii	Douglas Fir	6,500			4,000		2,500
hamnus purshiana	Cascara	3,1 <mark>5</mark> 0			2,000		1,150
Thuja plicata	Western Red Cedar	2,700	500	200	1,200	200	60 <mark>0</mark>
suga heterophylla	Western Hemlock	650			500		150
	Total Trees	<b>41,95</b> 0	<b>10,3</b> 00	5,600	<b>14,2</b> 00	<b>5,1</b> 00	6,750
Cornus sericea	Red Osier Dogwood	8,150	3,500	2,000	500	2,000	150
olodiscus discolor	Oceanspray	2,250			1500		750
Mahonia aquif <mark>o</mark> lium	Tall Oregon Grape	8,750	500	250	4500	1,000	2,500
Oemleria cerasiformis	Indian Plum	1,500			1000		<u>500</u>
Physocarpus capitatus	Ninebark	6,250	2,000	1,000	1500	1,000	750
Ribes sanguineum	Red flowering currant	1,000			1000		
Rosa nutkana	Nutka Rose	1,700			1200		500
Rosa pisocarpa	Swamp Rose	4,200	1,500	750	1000	750	200
Rubus parviflorus	Thimbleberry	2,200			1800		400
Salix lasiandra	Pacific Willow	3,750	1,500	750		1,500	
Salix scouleriana	S couler Willow	1,700			1500		200
Salix sitchensis	Sitka Willow	2,500	1,000	500		1,000	
Sambucus cerulea	Blue Elderberry	2,250			1500		750
ambucus rac <mark>e</mark> mosa	Red Elderberry	2,650	500	250	500	1,200	200
Spiraea douglasii	Spiraea	5,200	3,000	2,200			
Symphoriocarpus albus	Snowberry	8,800	1,000	1,100	4000	1,100	1,600
SHRUB TOTAL		62,850	14, <mark>5</mark> 00	<b>8,8</b> 00	21,500	9,550	<mark>8,5</mark> 00
PLANT TOTAL		104,800	24,800	14,400	35,700	14,650	15,250

**REVEGETATION UNITS SPECIES COMPOSITION** 

**RIVER ISLAND NORTH PRELIMINARY DESIGN** Metro



METRO **CLACKAMAS COUNTY, OREGON** 



### REVEGETATION **SPECIFICATIONS**

V2 OF 29

SHEET

# **PERMIT SUBMITTAL**